# **Goreway Station power plant**



**Location** Brampton, Ontario

**General contractor** Sithe Global

**Engineering firm** SNC Lavalin

**Distributor** Multiurethanes Ltd.

**Product used** Azo-Grout<sup>™</sup> 443 by Azon



Figure 1 Goreway Station power plant under construction.

#### Situation

The Goreway Station power plant is one of Ontario's biggest construction projects. Engineering, procurement and construction of the plant will cost more than \$1 billion with construction scheduled to be complete by the end of 2008. The natural gas-fired 875 MW power plant project will be Canada's largest combined cycle power station and Ontario's first new major power station to be built in 25 years.<sup>1</sup>

During construction, the power plant was experiencing leaking concrete construction joints within various underground chambers and control rooms, as well as leaking underground utility ductwork for electrical service lines for plant maintenance operations.

### Action plan

Multiurethanes was asked to assist SNC by devising methods to quickly and permanently resolve water infiltration problems at the new power plant. Multiurethanes submitted a plan of polyurethane injection utilizing Azo-Grout<sup>™</sup> 443. Once the plan was approved, specialized injection equipment and experienced technical personnel were provided on the job site during the injection process.

#### About the product

Azo-Grout<sup>™</sup> 443 by Azon is a medium viscosity, water-activated hydrophobic polyurethane grout that is used in various concrete construction applications to permanently resolve common water infiltration problems.

#### Outcome

Water inflow problems were successfully overcome through systematic injection of concrete structural joints and through sealing around the utility ductwork associated with the underground vaults.

<sup>&</sup>lt;sup>1</sup>Versace, Vince. "Electrifying project shocks all." <u>Daily Commercial</u> <u>News and Construction Record online</u>. 11 July 2007. 9 January 2008 <a href="http://www.dcnonl.com/article/id23578">http://www.dcnonl.com/article/id23578</a>>.







## **Goreway Station power plant**





Figure 2 Preparing to enter the leaking manhole vaults during the injection process.



Figure 3 Close-up of the injection site.

**WARRANTY** The information contained in this document is to assist customers in determining whether our products are suitable for their applications. Our products are intended for sale to industrial and commercial customers. The customer must inspect and test our products before use, and satisfy themselves as to the contents and suitability. Nothing herein shall constitute a warranty, expressed or implied, including any warranty of merchantability or fitness, nor is protection from any law or patent to be inferred. All patent rights are reserved. The exclusive remedy for all proven claims is replacement of our materials, and in no event shall we be liable for special, incidental or consequential damages.

©Azon 2010 AGCS2 Page 2 of 2







**Azon**, 643 W. Crosstown Parkway, Kalamazoo, MI 49008-1910 Tel: 269 385 5942 • Fax: 269 373 9295 • www.azonintl.com